

Your Building Summary

CUSTOMER INFORMATION

first name last name

GJunk@MargateFL.com

9548843678

Delivery Address:

33063 - Broward County, FL 33063

[Link to](#)

Created Mar 05, 1

Proposal based on building deliv

BUILDING SPECS

| | |
|----------------|----------|
| Width | 30ft |
| Length | 40ft |
| Eave Height | 10ft |
| Roof Pitch | 3/12 |
| Square Footage | 1200sqft |

CODES AND LOADS

The codes and building loads shown in this document are based on information provided to Allied or on readily available databases and are the basis for the price shown. Local jurisdictions may have amendments that alter building codes and loads, the purchaser should verify the applicability of the below stated codes and loads.

| | |
|-----------------|----------|
| Building Code | IBC |
| Roof Live Load | 20 psf |
| Collateral Load | 2 psf |
| Wind Speed | 168 mph |
| Wind Exposure | C |
| Wind Enclosure | Enclosed |
| Ground Snow | 0 psf |

Need help?
[Click here for support.](#)



| | |
|---------------------|---------------------|
| Estimated Roof Snow | 0 psf |
| Seismic Parameters | Ss: 0.045 SI: 0.022 |
| Seismic Site Class | D |
| Occupancy Group | II |



(754)

Itemized Cost

TO

Colors

- Walls - Aqua
- Roof - Stone
- Trim - Stone

Subtotal

Accessories

Roof Insulation:
VRR Faced Blanket Fiberglass

Wall Insulation:
VRR Faced Blanket Fiberglass

Endwall Overhang: 1'
Soffit panels not included

Sidewall Overhang: 2'
Soffit panels not included

Gutters and Downspouts

Subtotal

Openings

3' x 3' Non-Insulated Window
Horizontal slider, aluminum white frame, clear glass. Framed opening included.

3' x 7' Non-Insulated Walk Door
Solid knock down, lever lock hardware. Field Located.

8' x 8' Framing Only
Metal jambs, header, full cover trim and fasteners. Door not included.

Subtotal

Need help?
Click here for support.



qty 3

qty 2

qty 2

Total Price and Deposit

BUILDING COST

Building Cost

| | |
|---------------|-------------|
| Base Building | \$24,269.78 |
| Openings | \$3,188.90 |
| Accessories | \$0.00 |
| Colors | \$408.19 |

Total **\$29,345.56**

*Real-time price is displayed
Price may be adjusted daily until purchase
Applicable taxes, if any, will be added to the final invoice*

Need help?
[Click here for support.](#)



Shipping included for continental US deliveries. Estimated at today's fuel rates. Subject to change at the time of delivery.

Deposit Due Today **\$2,934.56**

Payment Schedule

- 10% Design Payment, due at signing
- 50% Fabrication Payment, due on delivery of plans
- 40% Final Payment, due prior to delivery

Deposit Details

After deposit you will receive scope approval drawings within three to five business days. Your deposit is fully refundable, less a \$500 fee for the drawings if you cancel prior to engaging our project management team in the definitive design work. For further information, please see our [terms and conditions](#).

BUILDING KIT

Materials Included

- Commercial I-beam frames, grey primer
- 26 gauge PBR roof and wall panels
- All necessary roof and wall supports, pre-galvanized
- All necessary hardware, nuts and bolts
- Heavy Industrial X-Bracing
- Base and eave closures
- Complete full cover trim package
- Carbon Steel Fasteners with a lifetime warranty
- Pre-welded clips for easy erection, all pre-cut

Allied's Benefits included

- Anchor bolt setting plan with reactions, plans and elevations
- Certified stamped engineered drawings, to meet or exceed all municipal/local structural building codes, customer required to verify building codes
- Letter of Certification, *calculations available upon request*
- Erection manual
- 25-50 year panel warranty, dependent on color selection
- Extended warranty available
- Refundable deposit*
- Dedicated project manager throughout the life of the project

Need help?
Click here for support.



Bracing has been considered in the design based on the local building code applicable within your zip code and opening locations. Locations and bracing shown on the scope drawings presented post sale.

Exclusions from proposal

*Foundation design, Anchor Bolts, Erection

Sample Project Timeline

Order Execution & Clarification (+/-1 Week)

Meet your project manager within two business days of order execution to clarify building details and accessories. Receive your app drawings and invitation to Allied's client portal. We will work with you to outline your project milestones and set a project timeline the best for you.

Design & Engineering (2-3 weeks)

We will issue your certified stamped engineered drawings, including an Anchor Bolt Plan. Timing will vary based on the complexity of building design.

Detailing & Fabrication (4-5 weeks)

Once we receive your approval, our engineering team will specify the member sizes, material tolerance, manufacturing information fabrication will begin. Due to current high demand the fabrication schedule will be evaluated and shared by the project manager once order is executed.

Delivery (1-4 days)

Total project lead time is between 8-16 weeks. Timelines may vary based on time of year and manufacturing capacity. Your project manager will provide a tentative schedule outlining the milestones that must be met in order to meet this deadline. Please note, your permit lead times may affect this schedule.

Need help?
[Click here for support.](#)

