



To: City of Margate

September 30, 2024

Quote # 1985

ATTN: Mr. Pedro Stiassni

**RE: WTP EAST ACCELERATOR REPAIRS
CITY OF MARGATE, FLORIDA**

Our price includes supplying of all labor, materials, and equipment to complete the work as described below, **with the exclusion mentioned below.**

Our price includes:

Move in of equipment and materials

Interior concrete work:

Supply and set up of scaffolding for the duration of the project

Set up of the containment tarp

Hydro blasting of the concrete walls and 16-20" of the floor to SSPC CSP 3-4

Sawcut the keyway in the floor to tie in the coatings for full seal

Cutting out all visible cracks and repairing with Xypex patch and plug

Application of Sika top 107, first coat broomed into the concrete, second coat trowel on to semi smooth finish

Total price for interior concrete:

\$ 319,220.00

