

***Memorandum***

To: Ms. Angela Gargin  
Living Water Construction

From: J. Suzanne Danielsen, P.E.

Date: January 29, 2019

**Re: Popeye's Louisiana Kitchen - Margate, FL  
Trip Generation and Queuing Analysis**

As requested, Danielsen Consulting Engineers, Inc. (DC Engineers, Inc.) has prepared a trip generation and queuing analysis specific to the proposed Popeye's Louisiana Kitchen to be constructed along the east side of SR 7 (US 441) immediately north of SW 8 Court within municipal limits of the City of Margate, Florida. This study addresses trip generation and drive-through lane queuing characteristics for the proposed restaurant.

**TRIP GENERATION ANALYSIS**

A current site plan, included as Attachment A, shows a 2,466 square foot fast food restaurant with two (2) drive-through lanes. Upon buildout of the proposed restaurant, access will be provided through three (3) driveways as follows: one (1), two (2)-way driveway along SW 8 Court, one (1) entrance only driveway along the west property line and one (1), two (2)-way cross access driveway along the north property line.

**Trip Generation**

A trip generation analysis has been completed for the proposed restaurant. The analysis was performed using rates and formulae published in the Institute of Transportation Engineer's (ITE) report *Trip Generation* (10th Edition). The trip generation analysis was undertaken for daily and PM peak hour conditions. An AM analysis has not been considered as the restaurant, opening at 10:30 AM, will not impact the AM peak hour of the adjacent roadway network. According to the referenced ITE report, the most appropriate land use category and corresponding rates for the proposed development are as follows:

**Fast-Food Restaurant with Drive-Through Window - ITE Land Use #934**

Daily Trips:  $T = 470.95(X)$  (50% inbound and 50% outbound)  
where  $T$  = number of trips and  $X$  = 1,000 square feet gross floor area

PM Peak Hour Trips  $T = 32.67(X)$  (52% inbound and 48% outbound)

The results of this effort are documented in Table 1 included as Attachment B. As shown in Table 1, the proposed restaurant is expected to produce 1,161 vehicle trips per day with 81 vehicle trips occurring during the PM peak hour (42 entering and 39 exiting).

**Queuing Analysis**

As shown in the site plan included as Attachment A, the proposed Popeye's Louisiana Kitchen includes a drive-through lane that widens to two (2) parallel lanes at the menu board and then merges back to one (1) lane prior to the pick-up window. This double menu board arrangement is intended to increase efficiency of the drive-through operation and to maximize the stacking capacity.

The length of queue anticipated within the drive-through lane(s) was determined using methodologies contained in ITE's *Transportation and Land Development*, Chapter 8 - Drive-In Facilities. For this analysis, the following input variables were used:

- Service Rate: The average window transaction time is estimated to be 60 seconds consistent with information provided in *Transportation and Land Development*.
- Demand Rate: Based on ITE's *Trip Generation* (10th Edition), the maximum inbound vehicular traffic flow anticipated at a 2,466 square foot fast food restaurant is 42 vehicles (refer to trip generation section above). Although ITE estimates that 45 percent of inbound vehicular traffic uses drive-through lanes, to provide a conservative analysis this queue analysis assumes 100 percent of inbound vehicles will use the drive-through lanes.

Using equation 8-9b and Table 8-11 of ITE's *Transportation and Land Development*, the maximum length of queue anticipated within the drive-through lane(s) is two (2) vehicles. Calculations are included as Attachment C. As the site plan provides in excess of 44 feet of stacking space (22 feet per vehicle queued), vehicular queuing outside of the stacking area proposed is not expected.

**Conclusion**

In summary, the Popeye's Louisiana Kitchen as proposed is expected to have adequate storage to accommodate peak inbound vehicular demands anticipated within the drive-through lane(s).


Of course, please do not hesitate to contact me directly with any questions you may have.

Sincerely,

**DC ENGINEERS, INC.**





J. Suzanne Daniels, P.E.  
Senior Transportation Engineer



J. Suzanne Daniels, P.E.  
Florida Registration Number 42533  
Danielsen Consulting Engineers, Inc.  
12743 NW 13th Court  
Coral Springs, FL 33071  
CA # 3202

**Attachment A**  
Site Plan

---



**SITE DATA**

CURRENT USE:	VACANT
LAND USE DESIGNATION:	TOC
ZONING DESIGNATION:	TOC-C
WATER SERVICE PROVIDER:	CITY OF MARGATE
WASTEWATER SERVICE PROVIDER:	CITY OF MARGATE

BUILDING HEIGHT:	21'-4"
BUILDING LENGTH:	82'
NUMBER OF STORIES:	1 STORY
GROSS FLOOR AREA:	2,137 SF

	SF	ACRES	PERCENTAGE
LAND AREA	44,085.50	1.01	100
PROP. BLDG	2,466	0.06	5.59
ASPHALT	21,493	0.49	48.75
SIDEWALK	3,877	0.09	8.79
TOTAL IMPERVIOUS	27,836	0.64	63.14
PERVIOUS	16,249.50	0.37	36.86

**PARKING REQUIRED**  
 1 SPACE PER 50 SF OF GROSS FLOOR AREA: 895 SF / 50 = 18 SPACES

**PARKING PROVIDED**

STANDARD	= 24 SPACES
SPACE DESIGNATED FOR SELF STORAGE	= 1 SPACE
HANDICAP SPACES	= 2 SPACE
TOTAL PROVIDED	= 27 SPACES

**NOTE:**  
 ALL TRAFFIC CONTROL PAVEMENT MARKINGS WILL BE THERMOPLASTIC.

Curve Table

Curve #	Length	Radius	Delta
C1	32.987	21,000	090.0000
C2	79.751	24,000	190.3917
C3	17.920	14,000	073.3367
C4	12.783	17,500	041.8511
C5	12.482	17,500	040.8678

Line Table

Line #	Length	Direction
L1	25.518	N01° 02' 11.61"W
L2	15.852	N55° 46' 32.10"W
L3	17.461	N90° 00' 00.00"E

REV.	DESCRIPTION	DATE
1		
2		
3		
4		
5		

IMTIAZ AHMED, P.E.  
 LICENSED ENGINEER NO. 46102  
 STATE OF FLORIDA

**METRO CHICKEN**  
 750 STATE ROAD 7  
 MARGATE, FLORIDA

POPEYES

ATLANTIC ENGINEERING SERVICES, INC.  
 200 C3 CROSSWINDS DRIVE  
 WEST PALM BEACH, FLORIDA 33413  
 PHONE - (561) 358-4140  
 FAX - (561) 966-9242  
 CERTIFICATE OF AUTHORIZATION NO.: 9390

PROJ. NO. 0000  
 SCALE: AS SHOWN

ddt		
DES.	DWN.	CHK.
SHEET NUMBER		
<b>SP1</b>		
DATE DRAWN MAR 2018		

SITE PLAN

**Attachment B**  
Trip Generation

---

**Table 1: Trip Generation Summary Proposed Uses**

Land Use	Scale	Units	AM Peak Hour			PM Peak Hour			Daily		
			Total Trips	Inbound	Outbound	Total Trips	Inbound	Outbound	Total Trips	Inbound	Outbound
Fast-Food Restaurant with Drive-Through Window (LUC 934)	2.466	ksf	NA	NA	NA	81	42	39	1161	581	580
<b>Total</b>			<b>0</b>	<b>0</b>	<b>0</b>	<b>81</b>	<b>42</b>	<b>39</b>	<b>1,161</b>	<b>581</b>	<b>580</b>

Source: ITE Trip Generation Manual (10th Edition)

T = 470.95(x)

50% in, 50% out

Daily

T = 32.67(x)

52% in, 48% out

PM Peak

**Attachment C**  
Queue Analysis

---

**Popeye's Louisiana Kitchen – Margate – Drive-Through Operations**  
**Queuing Analysis based on ITE Procedures**

$$q = 42 \text{ veh/hr (demand rate)}$$

$$Q = 60 \text{ veh/hr (service rate)}$$

$$p = \frac{q}{NQ} = 0.350 \text{ (N = 2)}$$

$$Q_M = 0.1836 \text{ (for N = 2)}$$

Using Acceptable Probability of 1% (99% Confidence Level)

$$M = \left( \frac{\text{Ln}(x > M) - \text{Ln}(Q_M)}{\text{Ln}(p)} \right) - 1$$

$$M = \left( \frac{\text{Ln}(0.01) - \text{Ln}(0.1836)}{\text{Ln}(0.350)} \right) - 1$$

$$M = \left( \frac{-4.605 - (-1.695)}{-1.0498} \right) - 1$$

$$M = 2.772 - 1 = 1.772 \text{ vehicles}$$

or, 2 vehicles