



Powering Business Worldwide

## Detail Bill of Material

Page 1 of 3

Project Name: City of Margate 250HP RVSS  
General Order  
No:

Negotiation No: MI850113X5K2  
Alternate No: 0000

Item No.	Qty	Product	Description	Unit Price	Extended Price
004	3	Engineering Services	STARTUP S811+ 1 Day Startup of S811+ Soft Starter, M-F, 8AM-5PM.	\$2,079.00	\$6,237.00

Catalog No STARTUP  
Designation Startup

Item No.	Qty	Product	Description	Unit Price	Extended Price
005	3	Engineering Services	EXTENDED WARRANTY 36 Months Extended Warrantyr (Parts Only) from Date of Order Shipment.	\$473.40	\$1,420.20

Catalog No EXTENDED WARRANTY  
Designation EXT WARRANTY

Item No.	Qty	Product	Description	Unit Price	Extended Price
001	1	Motor Control Centers	60 Hz, Class 1B wiring, 480V 3-Phase Service, 65,000 Bracing, Top Incoming, NEMA 1 Gasketed 21" Front Mt Only enclosure, 600A Copper Main Horizontal Bus, No Neutral, Main Lugs. Used X-Space: 12, Blank X-Space: 0, Future X-Space: 0, MCC Lead Time Code: B.	\$11,835.60	\$11,835.60

Designation Effluent Pump #2

### Qty List of Materials

- 1 #4-350 Kcmil 2/Ph Main Lugs (Screw)
- 1 IT Soft Start S811 Non-Communicating, 420 Amp, Standard Duty, [HMCP]
- 1 Panel Elapsed Time Meter (Standard)
- 1 Pilot Light-10250T - LED (Run)
- 1 3 Pos. Sel. Sw., 10250T (Hand-Off-Auto)
- 1 Pilot Light-10250T - LED (Stopped)
- 1 Terminal Block - Latching Pull-Apart, Std.
- 1 Wiremarkers at Each End
- 1 #16awg, MTW Control Wire
- 1 IT Soft Start Pump Control Software Option
- 1 IT Soft Start 120V Interface & 150VA CPT
- 1 Additional X-Space
- 1 IT Soft Start SSRV, MOV Surge Suppressor
- 1 Wiring Diagram on Door
- 1 300A Horiz. Cu Gnd Bus, 1/4" x 1" Bar
- 1 65KA Bus Bracing
- 1 Labyrinth, Isolated/Insulated vertical bus barrier with shutters
- 1 8 Inch Wide Vertical Wireway, in lieu of 4 inch.
- 1 600A Vertical Bus (Tin-plated cu)
- 1 Tin Plated horizontal bus
- 1 600A Copper Frnt Mtd 21" NEMA 1 Gasketed



Powering Business Worldwide

## Detail Bill of Material

Page 2 of 3

Project Name: City of Margate 250HP RVSS  
General Order  
No:

Negotiation No: M1850113X5K2  
Alternate No: 0000

Item No.	Qty	Product	Description	Unit Price	Extended Price
002	1	Motor Control Centers	60 Hz, Class 1B wiring, 480V 3-Phase Service, 65,000 Bracing, Top Incoming, NEMA 1 Gasketed 21" Front Mt Only enclosure, 600A Copper Main Horizontal Bus, No Neutral, Main Lugs. Used X-Space: 12, Blank X-Space: 0, Future X-Space: 0, MCC Lead Time Code: B.	\$11,835.60	\$11,835.60

Designation Effluent Pump #1

### Qty List of Materials

- 1 #4-350 Kcmil 2/Ph Main Lugs (Screw)
- 1 IT Soft Start S811 Non-Communicating, 420 Amp, Standard Duty, [HMCP]
- 1 IT Soft Start Pump Control Software Option
- 1 Pilot Light-10250T - LED (Run)
- 1 Pilot Light-10250T - LED (Stopped)
- 1 IT Soft Start 120V Interface & 150VA CPT
- 1 Wiremarkers at Each End
- 1 Wiring Diagram on Door
- 1 #16awg, MTW Control Wire
- 1 Terminal Block - Latching Pull-Apart, Std.
- 1 Additional X-Space
- 1 3 Pos. Sel. Sw., 10250T (Hand-Off-Auto)
- 1 IT Soft Start SSRV, MOV Surge Suppressor
- 1 Panel Elapsed Time Meter (Standard)
- 1 300A Horiz. Cu Gnd Bus, 1/4" x 1" Bar
- 1 65KA Bus Bracing
- 1 Labyrinth, Isolated/Insulated vertical bus barrier with shutters
- 1 8 Inch Wide Vertical Wireway, in lieu of 4 inch.
- 1 600A Vertical Bus (Tin-plated cu)
- 1 Tin Plated horizontal bus
- 1 600A Copper Frnt Mtd 21" NEMA 1 Gasketed

SBI 042

Item No.	Qty	Product	Description	Unit Price	Extended Price
003	1	Motor Control Centers	60 Hz, Class 1B wiring, 480V 3-Phase Service, 65,000 Bracing, Top Incoming, NEMA 1 Gasketed 21" Front Mt Only enclosure, 600A Copper Main Horizontal Bus, No Neutral, Main Lugs. Used X-Space: 12, Blank X-Space: 0, Future X-Space: 0, MCC Lead Time Code: B.	\$11,835.60	\$11,835.60

Designation Effluent Pump #4

### Qty List of Materials

- 1 #4-350 Kcmil 2/Ph Main Lugs (Screw)
- 1 IT Soft Start S811 Non-Communicating, 420 Amp, Standard Duty, [HMCP]
- 1 IT Soft Start Pump Control Software Option
- 1 Pilot Light-10250T - LED (Run)
- 1 Pilot Light-10250T - LED (Stopped)
- 1 IT Soft Start 120V Interface & 150VA CPT
- 1 Wiremarkers at Each End
- 1 Wiring Diagram on Door
- 1 #16awg, MTW Control Wire
- 1 Terminal Block - Latching Pull-Apart, Std.
- 1 Additional X-Space
- 1 3 Pos. Sel. Sw., 10250T (Hand-Off-Auto)
- 1 IT Soft Start SSRV, MOV Surge Suppressor
- 1 Panel Elapsed Time Meter (Standard)
- 1 300A Horiz. Cu Gnd Bus, 1/4" x 1" Bar



Powering Business Worldwide

## Detail Bill of Material

Page 3 of 3

Project Name: City of Margate 250HP RVSS  
General Order  
No:

Negotiation No: MI850113X5K2  
Alternate No: 0000

Qty	List of Materials
1	65KA Bus Bracing
1	Labyrinth, Isolated/Insulated vertical bus barrier with shutters
1	8 Inch Wide Vertical Wireway, in lieu of 4 inch.
1	600A Vertical Bus (Tin-plated cu)
1	Tin Plated horizontal bus
1	600A Copper Frnt Mtd 21" NEMA 1 Gasketed

Eaton Selling Policy 25-000 applies.

Total Quoted Price- \$43,164.00

All orders must be released for manufacture within 90 days of date of order entry. If approval drawings are required, drawings must be returned approved for release within 60 days of mailing. If drawings are not returned accordingly, and/or if shipment is delayed for any reason, the price of the order will increase by 1.0% per month or fraction thereof for the time the shipment is delayed.