

A R C H I T E C T U R E, I N C.	
HAROLD TUTTLE AR #0015395	
JONATHAN THOMAS	
ANNE MARIES RESTAURANT 2403 STATE ROAD #7 MARGATE, FLORIDA	
REVISIONS DAT	E
	_
Contract	
Permit Bid	
Date 4/1/14	
Scale AS NOTED	
Drawn HT Job 2013-123	
Sheet	
A2.01 Of X/X Sheets	

POURED IN PLACE CONCRETE

- 1. POURED IN PLACE CONCRETE MEMBERS ARE DESIGNED ON THE BASIS OF ULTIMATE STRENGTH DESIGN IN ACCORDANCE WITH ACI 318-05,
- "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE."
 POURED IN PLACE CONCRETE WORK SHALL BE PROPORTIONED IN ACCORDANCE WITH ACI 301, "SPECIFICATIONS FOR STRUCTURAL CONCRETE." THE FOLLOWING CONCRETE SPECIFICATIONS SHALL BE PRODUCED AT 28 DAYS:

MEMBER	STRENGTH (PSI)	MAXIMUM AGG. SIZE	MAXIMUM W/C RATIO
BEAMS	3000	3/4"	0.60
COLUMNS	3000	3/3"	0.60
GROUTED CELLS	3000	3/8"	0.60

- 3. DESIGN MIXES SHALL MEET OR EXCEED THE SPECIFICATIONS PROVIDED. WHERE STRENGTH AND WATER-CEMENT RATIOS ARE PROVIDED, THE MOST STRINGENT SHALL GOVERN
- MOST STRINGENT SHALL GOVERN. 4. CONCRETE SLUMP LIMITATIONS SHALL BE 4" MINIMUM, AND 6" MAXIMUM SLUMP LIMITATIONS FOR MASONRY GROUTED CELLS SHALL
- MAXIMUM. SLUMP LIMITATIONS FOR MASONRY GROUTED CELLS SHALL BE 9" MAXIMUM.
- 5. UNDER NO CIRCUMSTANCES SHALL WATER BE ADDED TO A CONCRETE MIX AFTER CONCRETE HAS BEEN DISCHARGED FROM THE BATCH PLANT.
- POURED IN PLACE CONCRETE TRANSPORTED AT THE JOB BY CONCRETE PUMP SHALL BE DESIGNED ACCORDINGLY.
 ALL POURED IN PLACE CONCRETE SHALL BE CONSOLIDATED THROUGH
- ALL POURED IN PLACE CONCRETE SHALL BE CONSOLIDATED THROUGH THE USE OF MECHANICAL VIBRATORS.
 CONCRETE COVER TO REINFORCING STEEL SHALL BE IN ACCORDANCE
- WITH ACI 318, WITH THE FOLLOWING MINIMUM REQUIREMENTS: SLABS

BEAMS AND COLUMNS	1-1/2"
FORMED CONCRETE BELOW GRADE	2"
CONCRETE CAST AGAINST SOIL	3"

9. POURED IN PLACE CONCRETE SHALL BE CURED IN ACCORDANCE WITH ACI 318. CURING COMPOUNDS SHALL BE APPLIED THE SAME DAY THE CONCRETE IS POURED, ONCE THE CONCRETE HARDENS, AND AS WEATHER CONDITIONS MAY DICTATE. FOLLOW MANUFACTURER'S RECOMMENDATIONS WHEN APPLYING CURING COMPOUNDS.

